# CITY OF PORT ANGELES

Lincoln Street - Peabody Creek Culvert



Jonathan Boehme, P.E. City Engineer

## PORT ANGELES OVERVIEW


Strait of Juan de Fuca

**Port Angeles Harbor** 

**5** Creeks

**Olympic Mountains** 





- Case Study: Creek through middle of City
- > Unique Factors:
  - On State Fish Passage Injunction List
  - Multi-jurisdictional (City and WSDOT)
  - Culvert daylight problematic (R/W, Street Connectivity, limited habitat)
  - Prioritization and habitat potential among area creeks



## PEABODY CREEK LINCOLN ST CULVERT

#### Peabody Creek Basin

- Extends through the middle of the downtown business district
- Final 1,070 in structurally deficient culvert
- Culvert on injunction list
- Creativity beyond typical open cut



## PEABODY CREEK CULVERT



Picture 8: Construction of culvert north at intersection of Front and Lincoln (looking south)



Picture 10: Port Angeles regrading





## HISTORICAL PHOTOS



Figure 2-9. Ellipse: crack with infiltration (335')

Figure 2-10. Ellipse: crack with infiltration

## CULVERT OBSERVATIONS





Figure 3-1. Void locations at the intersection of Lincoln Street and First Street

- High potential for structural failure
- > 2012 8 foot sinkhole was identified and filled at the intersection of Lincoln St and First St
- > 2014 Ground penetrating radar identified 4 voids in close proximity to the culvert
- > 2019 Inspection of culvert revealed no significant changes in condition

CULVERT OBSERVATIONS







#### 2009 Scoping level concepts evaluated including open cut and repair alternatives

- > 2013 State Fish Passage Injunction
- > 2014 City Study identify's four voids in close proximity to culvert
- 2016 City identify's preliminary design funding to accelerate project, Meets with Stakeholders WSDOT, LEKT and USACOE
- 2019 City Environmental and Permitting coordination and interest in accelerating nearby Ennis Creek Restorations




#### EPOXY GRIP ANCHOR EVERY 10' WELDED 3/4-10 COUPLING NUT EPOXY GRIP ANCHOR EVERY 10' CMP 12" SCHEDULE 12" SCHEDUL 40 PVC 12 12" SCHEDULE 40 PVC PIPE HANGER 40 PVC PIPE HANGER 12" PIPE HANGER TEMP, LIGHT TEMP, LIGH TEMP. LIGHT WELDED STUD (TYP.) -4" SHOTCRETE 4" SHOTCRETE -4" SHOTCRETE -FIRST 165 1.84' 1.84 .... WELDED WIRE REINFORCEMENT WELDED WIRE REINFORCEMENT REPAIR AREA WITH ATTACHMENTS WELDED WIRE REINFORCEMENT CL 3000 CONCRETE REPAIR AREA FIRST 165' WITH ATTACHMENTS RESTORE ORIGINAL FLOW LINE CL 3000 CONCRETE FIRST 165' RESTORE ORIGINAL FLOW LINE SECTION A SECTION B (NOT TO SCALE) SECTION C EXISTING 8' CMP (NOT TO SCALE) (NOT TO SCALE) notean STA 0+00 TO STA 1+80 EXISTING 8' CONCRETE PIPE EXISTING CONCRETE BOX (STATIONING BEGINS AT INLET) STA 1+80 TO STA 6+80 STA 6,+80 TO STA 10+80

#### PEABODY CREEK / LINCOLN STREET CULVERT REHAB

- Stakeholder buy in of repair with in place concepts and fish baffles
- Finalize Design
- Secure construction funding for Peabody Culvert Repair and Ennis Creek Culvert Replacement

Project Status: Preliminary Design (2019/2020) Total Construction Project Cost: \$3.0 million


PEABODY CREEK / LINCOLN STREET CULVERT REHAB NEXT STEPS



- City Double Barrel Culvert Replacement
- WSDOT Culvert
   Replacement upstream
- High habitat potential in Ennis Creek Watershed

Project Status: Unfunded
Project Cost: \$0.5 million

ENNIS CREEK CULVERT REPLACEMENT



#### Questions & Discussion

THANK YOU