### **Joint Transportation Committee**

**Efficiencies in the Construction and Operation of State Transportation Projects** 

Presentation to the JTC, October 9, 2013



# October 9 Meeting Objectives

- Provide an update on progress and next steps
- Preview initial findings to date
- Discuss next steps



# Study Objectives


- To develop a broad understanding of the costs of transportation projects and what drives these costs
- To identify potential efficiency measures or reforms
- Results of this effort will support policy discussions regarding potential transportation funding package

#### Study Key Questions

- Do transportation projects in Washington State cost more than they do in other states?
  - If yes, why?
- What can we do?
  - Legislative action
  - WSDOT action



#### Project Status Update







### Project Status Update

| Advisory Panel 2 – Sept 30   | Advisory Panel 3 – Oct 29   | Advisory Panel 4 – Dec 3  |
|--|---|---|
| Cost Analysis  | <ul> <li>Contracting</li> </ul>   | <ul> <li>Review final assessment</li> </ul>                           |
| <ul> <li>WSDOT historical<br/>expenditures</li> </ul>                                      | <ul><li>- Method</li><li>- Risk assignment</li></ul>  | <ul> <li>Discuss potential policy choices and implications</li> </ul> |
| <ul> <li>- Mitigation</li> <li>• Sales &amp; Use Tax</li> <li>• Prevailing Wage</li> </ul> | <ul> <li>Closure windows</li> <li>OMWBE/DBE</li> <li>Permitting, Environmental Review and Mitigation</li> <li>Funding</li> <li>Method</li> <li>Federal requirements</li> <li>Availability</li> <li>Right of Way Acquisition</li> <li>Comparative Costs</li> </ul> | Discuss potential recommendations related to changes in practice      |



### Cost Analysis Introduction

- Understand how highway construction funds have been spent over the last decade
  - What are the biggest expenditure areas?
  - How have expenditures changed over time?
- A broad understanding of spending patterns will allow us to drill down into the costs behind specific drivers (for example, payments to prime contractors)
- This analysis focuses on the Preservation and Improvement Programs at WSDOT, which encompass the majority of highway construction projects




## Cost Analysis Available Information

- To begin to understand the potential impact of individual cost drivers, an assessment of historical WSDOT spending was conducted
- Foundation for this analysis is a database provided by WSDOT:
  - The database includes all projects in the Preservation and Improvement Programs that were marked as operationally complete from 2003-2012
  - The database does <u>not</u> includes expenditures on projects that are not yet complete, such as the 520 bridge
- The database includes a total of 2,293 projects and \$10.5 billion in expenditures

| Proje     | Project Cost |                       | Percent of | Project       | Percent of   |
|-----------|--------------|-----------------------|------------|---------------|--------------|
| Min       | Max          | Number of<br>Projects | Projects   | Expenditures  | Expenditures |
| Less th   | nan \$1 M    | 1,308                 | 57%        | \$ 522.2 M    | 5%           |
| \$ 1.0 M  | \$ 5.0 M     | 718                   | 31%        | \$ 1,594.3 M  | 15%          |
| \$ 5.0 M  | \$ 25.0 M    | 198                   | 9%         | \$ 2,199.9 M  | 21%          |
| \$ 25.0 M | \$ 100.0 M   | 53                    | 2%         | \$ 2,597.3 M  | 25%          |
| \$100 N   | 1 or more    | 16                    | 1%         | \$ 3,560.2 M  | 34%          |
|           | TOTAL        | 2,293                 | 100%       | \$ 10,473.9 M | 100%         |



# Cost Analysis Costs by Component



#### **Project Costs by Major Project Phase**

- Approximately 84% of expenditures (\$8.8 billion) in the database were spent on construction
  - Construction as a proportion of total project costs decreased from 91% in 2003 to 77% in 2012, primarily due to the impact of larger projects with greater right-of-way and predesign costs
  - Within construction costs there are payments to contractors (including sales tax, materials, supplies, labor, and overhead) and costs incurred by WSDOT on construction, oversight, testing, and inspection.
- Non-construction costs were 16% of expenditures (\$1.6 billion)
  - Right of way (6%, or \$638 million) and Engineering & Design (5%, or \$513 million) were the largest non-construction expenditures
- These definitions and costs are still being refined to better align WSDOT's cost tracking systems with the questions being asked in the study




## Cost Analysis Available Information

- BERK has worked with WSDOT to align expenditure categories with the phases that the JTC is interested in analyzing
  - In some cases, WSDOT categories align well with expenditure areas we are interested in, such as right of way acquisition
  - In other cases, it is challenging to identify and summarize certain types of expenditures.
  - Mitigation is one example where the data has been supplemented by WSDOT case studies. Mitigation costs are included in many project phases, from predesign up through construction



## Mitigation Introduction



- Defining mitigation can be a subjective exercise that generates disagreement about what should or should not be considered mitigation. Mitigation, depending on how it is defined, can include many aspects of a project:
  - Mitigation can take the form of design changes during the environmental review or permitting process to avoid environmental impacts. Sometimes these design changes add to overall project costs. These mitigation costs are difficult to track in a database
  - Some projects have impacts that need to be mitigated, which become requirements of the project. Since they are done in concurrence with other project design and construction activities, it is difficult to separate these costs from general project costs
  - WSDOT also does some projects where the whole project can be considered mitigation-like, even though the project may not be mitigating a specific concurrent project

## Mitigation WSDOT Case Studies

46 projects totaling almost \$2 billion in project costs were evaluated in four separate studies.
 Within the selected sample, 16% of project expenditures went to mitigation elements, with a significant range among individual projects of between 2% and 45%

| Study Period | Projects<br>Analyzed | Total Project<br>Cost | Total<br>Mitigation | Average<br>Mitigation | Range of Mitig | gation Percents |
|--------------|----------------------|-----------------------|---------------------|-----------------------|----------------|-----------------|
|              |                      |                       | Cost                | Percent               | Low            | High            |
| 2003         | 14                   | 426,868,000           | 78,304,000          | 18%                   | 2%             | 34%             |
| 2006         | 7                    | 641,277,610           | 111,057,000         | 17%                   | 2%             | 24%             |
| 2009         | 14                   | 670,290,000           | 105,214,400         | 16%                   | 5%             | 35%             |
| 2013         | 11                   | 241,940,000           | 31,331,807          | 13%                   | 2%             | 45%             |
| TOTAL        | 46                   | 1,980,375,610         | 325,907,207         | 16%                   | 2%             | 45%             |

|                  | Types of Mitigation |                                   |                     |             |            |              |           |             |
|------------------|---------------------|-----------------------------------|---------------------|-------------|------------|--------------|-----------|-------------|
|                  | Stream              | Wetlands                          | Stormwater          |             |            | Aesthetics & |           |             |
| Study Period     | Protection          | Protection Restoration Facilities | <b>Dust Control</b> | Noise Walls | CSS        | Temporary    | Total     |             |
| 2003             | 17,915,000          | 19,859,000                        | 30,180,000          | 950,000     | 4,650,000  | 2,470,000    | 2,280,000 | 78,304,000  |
| 2006             | 5,574,000           | 14,206,000                        | 54,538,000          | 0           | 36,739,000 | 0            | 0         | 111,057,000 |
| 2009             | 7,567,000           | 19,330,000                        | 70,712,400          | 0           | 4,942,000  | 2,663,000    | 0         | 105,214,400 |
| 2013             | 2,571,447           | 14,597,147                        | 11,750,563          | 0           | 1,360,000  | 936,774      | 115,876   | 31,331,807  |
| TOTAL            | 33,627,447          | 67,992,147                        | 167,180,963         | 950,000     | 47,691,000 | 6,069,774    | 2,395,876 | 325,907,207 |
| Percent of Total | 10.3%               | 20.9%                             | 51.3%               | 0.3%        | 14.6%      | 1.9%         | 0.7%      |             |



# Mitigation Overall Cost Implications


 The table below shows a preliminary estimate of how the different components of mitigation we have looked at so far add up over the last decade

|  | Expenditures<br>(in YOE \$) |
|--|-----------------------------|
| Mitigation w/in 2006-13 Case Study Projects      | \$ 248 M                    |
| Expenditures on Mitigation-like Projects         | \$ 100 M                    |
| Subtotal: Identified Mitigation Expenditures     | \$ 348 M                    |
| Expenditures not included in above categories    | \$ 7,906 M                  |
| Assumed portion spent on mitigation              | 16%                         |
| Subtotal: Estimated Mitigation on Other Projects | \$ 1,260 M                  |
| Estimated Total Mitigation Expenditures          | \$ 1,608 M                  |
| Total project expenditures included in analysis  | \$ 9,559 M                  |
| Implied percent spent on mitigation              | 17%                         |

- This table assumes that the average case study mitigation percentage of 16% applies to projects for which we do not have specific mitigation cost data
- Overall, about 17% or \$1.6 billion of total project expenditures from 2003-2012 may be related to mitigation. This estimate is preliminary and will be refined for the next phase of mitigation conversation at the Advisory Panel meeting



### Sales & Use Tax Introduction



Construction cost driver – state and local sales & use tax on projects on state-owned highways – tax on:

- Prime contractor full contract price
- Prime and sub-contractor purchases of materials consumed during construction

| Estimated Sales & Use Tax Collected on Projects Completed in 2003-12 | Sales & Use Tax Deferred               |
|--|--|
| \$541 million  | Tacoma Narrows Bridge - \$57.6 million |
|  | 520 - \$140.9 million (estimated)      |

#### **Policy considerations**

- General fund revenue from state sales & use tax
- Local government revenue from local option sales & use taxes
- Sales tax deferrals Tacoma Narrows Bridge and 520
- Ability to tax federal construction contracts

# Sales & Use Tax Application

Based on ownership of the highway – higher tax for projects on state-owned highways

| Тах  | State-owr                                       | ned Highways - No Exemption  | City, County, Political Subdivision,<br>& Federal-owned Highways<br>Public Road Construction Exemption            |
|--|---|--|---|
| Sales & Use tax                                | <ul><li>Materia taxed</li><li>Materia</li></ul> | I to full contract price als that become part of the structure are not als used by contractor during construction t part of the structure) are taxed at purchase | <ul> <li>Not applied to full contract price</li> <li>All materials taxed at purchase</li> </ul>                   |
| B&O tax  |   | lassification prime contractor—0.00471 saling classification for subcontractors—   | <ul> <li>Public road classification</li> <li>For both prime contractors &amp; subcontractors – 0.00484</li> </ul> |
| State tax cost*<br>for \$1 million<br>contract | Sales tax - \$ Prime B&O Total - \$76,          | tax - \$4,710  | Sales tax - \$32,500 <u>Prime B&amp;O tax - \$4,840</u> Total - \$37,340  |
| *State sales tax rate of 6.5%                  |   | Labor & other – 50%  Consumed materials – 10%  Installed materials – 40%  (estimate cost distribution from contractor)   |   |



## Sales & Use Tax Other States

Variation in sales & use tax application – affects cost comparison with WSDOT projects

| Other states - statewide sales & use tax (or equivalent excise tax) | 44<br>(5 states no state sales tax) |   |          | WA - projects on state-owned highways |
|---|-------------------------------------|---|----------|---------------------------------------|
|   | Yes                                 |   | No       |                                       |
| Tax full contract amount  | 4                                   | 4 40 35 – no projects 4 – no public 1 – no highways/bridges |          | Yes                                   |
|   | All                                 | No tax  | Consumed |                                       |
| Tax materials   | 25                                  | 7   | 12       | Materials consumed                    |

#### Other state taxes

- Alabama 5% tax on gross receipts from state highway projects (funds pensions & mental health)
- Delaware No state sales tax 0.006537 tax on contractor gross receipts over \$100,000/month (excludes sub-contractor payments)
- Mississippi 3.5% tax on prime contractors >\$10,000 in lieu of sales & use tax
- Montana No state sales tax 1% license fee on publicly funded projects

#### Directing sales & use tax collected on state highway projects to transportation fund

 West Virginia directs sales & use tax collected on state highway projects — only collected on all materials not full contract amount — to transportation fund



## Sales & Use Tax Alternatives & Policy

#### **Policy Considerations**

- General fund loss of revenue
- Local governments loss of revenue (Streamlined Sales & Use Tax Agreement requires same tax basis)
- Ability to tax federal contractors Supreme Court decision can tax federal contractors on materials if not higher than tax on state contractors
- Tax deferrals Tacoma Narrows Bridge \$57.6 million due 11<sup>th</sup> year of operation/520 estimate of \$140 million deferred until 5<sup>th</sup> year of operation of the bridge deferred taxes to be paid by tolls

| Alt | Alternative – Sales & Use Tax  |              | Cost \$ in millions<br>(based on \$ collected 2003-12) |        |           |  |
|-----|--|--------------|--|--------|-----------|--|
|     |  | General Fund | Local  | WSDOT  | Risk      |  |
| 1.  | Exempt projects on state-owned highways (all materials & total contract amount)  | -\$396       | -\$238   | +\$534 | Higher    |  |
| 2.  | Extend public road construction exemption to state-<br>owned highways (tax all materials – no tax on total<br>contract amount) | -\$202       | -\$70  | +272   | No change |  |
| 3.  | Direct sales & use tax receipts to transportation  | -\$396       | No change  | +\$396 | No change |  |



# Prevailing Wage Application



#### Based on funding

- State rates apply to state-funded projects with no federal aid
- Federal rates apply to federal-aid projects
- State requirement pay state rate if higher than federal rate on federal-aid projects

#### Difficult to compare state and federal rates

- State rates holiday & overtime rates
- Federal rates zone differentials

| County | State Rate                                | Federal Rate – Highway Category (also building & heavy)   |
|--------|---|---|
| Adams  | Wage \$34.81<br>Holiday 7B<br>Overtime 1M | Wage \$24.10<br>Fringes \$10.65<br>Zone 2 (>45 miles from Pasco, Spokane, Lewiston) + \$2.00  |
| King   | Wage \$41.69<br>Holiday 7A<br>Overtime 2Y | Wage \$31.75 Fringes \$9.85 Zone 2 (w/in 25-45 miles of Seattle or Kent City Hall) + \$1.00 Zone 3 (> 45 miles from Seattle or Kent City Hall ) +\$2.00 |



# Prevailing Wage Other States

18 states – no state prevailing wage law

- 1 state with a prevailing wage law, does not have a state rate
- 2 states that set a state prevailing wage rate, exempt state transportation department

| Practices  | Washington  | 28 states that set state prevailing wage for transportation projects   |
|--|---|--|
| Threshold below which the wage is not in effect                | No threshold  | 17 – thresholds of \$25,000 to \$500,000<br>3 – thresholds of \$1,000 - \$2,000<br>8 – no threshold  |
| State rate used if higher than federal on federal-aid projects | Yes – must use higher rate  | <ul><li>14 – higher rate</li><li>9 – federal rate</li><li>4 – use federal rate as state rate</li></ul>   |
| State basis for determining rates                              | Survey every 3 years (goal - actually less frequently) & collective bargaining agreements | 4 – use federal rate as state rate 9 – collective bargaining agreements 13 – annual survey (1 of which – new law to use survey, or federal or a combination) |
| Highway worker category  | No  | 20 – yes (some combined with heavy)<br>8 – no  |



# Prevailing Wage Alternatives & Policy

Policy – Dept. of Labor & Industries Prevailing Wage Handbook

- Protect employees of public works contractors from substandard earnings
- Preserve local wages

| Alternative |   | Policy (projects & \$ based on 2003-12 experience)  | Cost Savings                             |
|-------------|---|---|--|
| 1.          | Exempt WSDOT projects from state prevailing wage act (retain federal prevailing wage on federal-aid projects) | 82% of projects have federal funding<br>18% would have no federal or state rate                                 | N/A<br>Studies vary widely               |
| 2.          | Exempt WSDOT federal-aid projects from state prevailing wage act (federal rate only on federal-aid projects)  | All projects would have either federal or state prevailing wage rate  | JLARC 1998 study<br>State rates higher   |
| 3.          | Set threshold for WSDOT projects below which no state prevailing wage   | If \$500,000 threshold:<br><2% of total project cost<br>9% of projects – no federal or state<br>prevailing wage | N/A<br>Studies vary widely               |
| 4.          | Use federal rate as state rate  | Retain state prevailing wage – alter how wage is set  | 0.44% state highway program – 1998 JLARC |
| 5.          | Other alternatives to set state rate a) Annual survey b) Collective bargaining agreements c) Highway category | Retain state prevailing wage – alter how wage is set  | N/A                                      |



# Other Cost Drivers Next Steps

- Contracting
  - Method
  - Risk assignment
  - Closure windows
  - OMWBE/DBE
- Permitting, Environmental Review and Mitigation
- Funding
- Right of Way Acquisition
- Comparative Costs



# Comparative Costs Approach

- A key question posed in this study is whether, and to what degree, WSDOT projects are more costly than those in other states
- Given the challenges of ensuring that project comparisons reflect truly comparable projects, we have chosen to address this question in two ways:
  - Identify key driver-level differences which could lead to significant cost differences between WSDOT projects and projects elsewhere
  - Conduct literature review and where appropriate provide a high level assessment of comparable project costs across states
- The driver-level analysis will explore how each cost driver impacts project costs overall and puts this into a broader state to state comparison
- Since data availability will be an issue in the driver-level analysis, we will
  ensure that every driver includes a comparison with Oregon and Utah to
  provide a complete top-to-bottom review with two western peer states



#### JTC Study Next Steps

- Continue analysis of costs and cost drivers
- Identify policy options
- October 29: Advisory Panel Meeting #3
- December 3: Advisory Panel Meeting #4
- December 12: Presentation to the JTC DRAFT final report
- January 8: Publish final report

